BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the work:- Improvements to drains of Vayunandhan Layout Cross roads in Kempapura in ward no.07, Byatarayanapura.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	297.83	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.143.Item No.19.1)	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
2	45.50	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . **(Pg.No.13, It.4.3)**	Cum	5408.12	Rupees Five Thousand Four Hundred Eight and Twelve Paise Only
3	606.60	Providing granite slabs of selected quality reoughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.7.5cms thick(Pg No.27, Item No.5.31.1)	Sqm	742.00	Rupees Seven Hundred Forty Two Only
4	1066.20	Providing granite slabs of selected quality reoughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 10cms thick (Pg No.27, Item No.5.31.2)	Sqm	966.72	Rupees Nine Hundred Sixty Six and Seventy Two Paise Only
5	161.46	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	2226.00	Rupees Two Thousand Two Hundred Twenty Six Only
6	12.00	KSRRB M2900-2.1. Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH Specification No. 1000,2300 Page No. 255, Item No. 34.7.8, PWD SR 2018-19	Mtr	5976.28	Rupees Five Thousand Nine Hundred Seventy Six and Twenty Eight Paise Only
7	1.36	Providing 100mm and down size nominal size. (Pg No.I.Item No.23)	Cum	987.62	Rupees Nine Hundred Eighty Seven and Sixty Two Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	0.90	Providing 40mm and down size nominal size (Pg No.II.Item No.25)	Cum	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only
9	0.90	Providing 20mm and down size nominal size (Pg No.II.Item No.28)	Cum	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only
10	0.68	Providing Fine aggrgate 2.36mm nominal size (Pg No.II.Item No.32)	Cum	1054.29	Rupees One Thousand Fifty Four and Twenty Nine Paise Only
11	297.83	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 136, item No. 17.1)	Cum	94.34	Rupees Ninety Four and Thirty Four Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.